

ROBOTY NA ZJAZDACH

Zał.12

Lp	Pikietaż	Strona	Promień R	Długość	Szerokość	Podbudowa gr.25 cm z kamienia łamanego 0/31	Nawierzchnia gr. 3 cm z masy mineralno- asfaltowej	Nawierzchnia gr. 15 cm z kamienia łamanego 0/31	Roboty ziemne
			m	m	m	m ²	m ²	m ²	m ³
1	2+150,00	L	5,0	10,0	2,5	32,4	30,4		20,0
2	2+222,50	L	3,0	1,5	4,5			10,5	2,0
3	2+232,00	L	3,0	1,5	4,5			10,5	2,0
4	2+268,00	L	3,0	1,5	4,5			10,5	2,0
5	2+317,00	L	3,0	1,5	4,5			10,5	2,0
6	2+323,00	L	3,0	1,5	4,5			10,5	2,0
7	2+351,00	L	3,0	1,5	4,5			10,5	2,0
8	2+385,00	L	3,0	1,5	4,5			10,5	2,0
9	2+412,00	L	3,0	1,5	4,5			10,5	2,0
10	2+447,00	L	3,0	1,5	4,5			10,5	2,0
11	2+475,00	L	3,0	1,5	4,5			10,5	2,0
12	2+489,00	L	3,0	1,5	4,5			10,5	2,0
13	2+550,00	L	3,0	1,5	4,5			10,5	2,0
14	2+562,00	L	3,0	1,5	4,5			10,5	2,0
15	2+161,00	P	5,0	10,0	4,0	54,8	50,8		20,0
16	2+163,00	P	3,0	4,0	4,5			21,8	5,0
17	2+193,00	P	3,0	5,5	4,5			28,6	7,0
18	2+195,00	P	3,0	4,0	4,5			21,8	5,0
19	2+238,50	P	3,0	2,0	4,5			12,8	3,0
20	2+255,00	P	5,0	10,0	4,0	54,8	50,8		20,0
21	2+260,00	P	3,0	4,0	4,5			21,8	5,0
22	2+328,00	P	5,0	10,0	4,0	54,8	50,8		20,0
23	2+349,00	P	3,0	2,0	4,5			12,8	3,0
24	2+402,00	P	3,0	2,0	4,5			12,8	3,0
25	2+427,00	P	3,0	2,0	4,5			12,8	3,0
26	2+434,5	P	5,0	10,0	5,0	54,8	50,8		20,0
27	2+439,5	P	3,0	4,0	4,5			21,8	5,0
28	2+500,00	P	5,0	10,0	4,0	54,8	50,8		20,0
29	2+565,00	P	3,0	2,0	4,5			12,8	3,0
30	2+588,00	P	3,0	2,0	4,5			12,8	3,0
Razem						306	284	329	191

Uwaga:

- 1) nawierzchnia z kostki betonowej gr. 8 cm na posypce cementowo-piaskowej gr. 3 cm, na podbudowie z kruszywa łamanego, grubość warstwy 25 cm
- 2) nawierzchnia z kruszywa łamanego 0/31, grubość warstwy 25 cm